

# HILL RIDGE HOMES CRANBERRY MARSH ESTATES TOWN OF COLLINGWOOD

## KEY PLAN




## INDEX

DWG NO.	DESCRIPTION
	TITLE PAGE AND INDEX
ESC-1	EROSION AND SEDIMENT CONTROL PLAN
ESC-2	EROSION AND SEDIMENT CONTROL DETAILS
SAN-1	SANITARY DRAINAGE PLAN
DP-1	PRE-DEVELOPMENT DRAINAGE PLAN
DP-2	POST-DEVELOPMENT DRAINAGE PLAN
PP-1	SITE SERVICING PLAN AND PROFILE
SG-1	SITE GRADING PLAN
DE-1	DETAILS & NOTES
E1.1	SINGLE DIAGRAM
E2.1	SITE PLAN - POWER LAYOUT
E3.1	SITE PLAN - LIGHTING LAYOUT
E3.2	LIGHTING DETAILS - SHEET 1
E3.3	LIGHTING DETAILS - SHEET 2
E4.1	SITE PLAN - PHOTOMETRICS LAYOUT


## LEGEND

PROPERTY LINE	---
EXISTING CENTERLINE	—
PROPOSED CENTERLINE	—
EXISTING EDGE OF ASPHALT	—
PROPOSED EDGE OF ASPHALT	—
EXISTING EDGE OF SHOULDER	—
PROPOSED EDGE OF SHOULDER	—
EXISTING DITCH/DIRECTION OF FLOW	—
PROPOSED DITCH/DIRECTION OF FLOW	—
EXISTING SANITARY SEWER/SIZE/DIRECTION OF FLOW	— 200 <sub>8</sub> SAN
PROPOSED SANITARY SEWER/SIZE/DIRECTION OF FLOW	— 200 <sub>8</sub> SAN
EXISTING SANITARY SERVICE	—
PROPOSED SANITARY SERVICE	— PLUG
EXISTING SANITARY FORCEMAIN/SIZE/DIRECTION OF FLOW	— 200 <sub>8</sub> SAN F/M
PROPOSED SANITARY FORCEMAIN/SIZE/DIRECTION OF FLOW	— 150 <sub>8</sub> W/M
EXISTING WATERMAIN/SIZE	— 150 <sub>8</sub> W/M
PROPOSED WATERMAIN/SIZE	— 150 <sub>8</sub> W/M
EXISTING WATER SERVICE	—
PROPOSED WATER SERVICE	—
EXISTING STORM SEWER/SIZE/DIRECTION OF FLOW	— 375 <sub>8</sub> STM
PROPOSED STORM SEWER/SIZE/DIRECTION OF FLOW	— 375 <sub>8</sub> STM
EXISTING CULVERT	—
PROPOSED SWALE LOCATION	—
PROPOSED CULVERT	—
PROPOSED JOINT HYDRO, BELL AND ROGERS	—
EXISTING GAS MAIN	—
PROPOSED GAS MAIN	—
EXISTING FENCELINE	—
PROPOSED FENCELINE	—
EXISTING BUSHLINE	—
EXISTING CONTOUR	— 179.00
EXISTING SPOT ELEVATION	× 179.00
PROPOSED SPOT ELEVATION	× 179.00
EXISTING GRADING DIRECTION	—
PROPOSED GRADING DIRECTION	—
PROPOSED SWALE LOCATION	—
EXISTING TEMPORARY BENCHMARK	• TBM
EXISTING STANDARD IRON BAR	• SIB
EXISTING BOREHOLE/NUMBER	◆ BH#
EXISTING GAS VALVE	◇ GAS
EXISTING HYDRO TRANSFORMER	⊠
EXISTING CABLE PEDESTAL	⊠
EXISTING BELL PEDESTAL	⊠
EXISTING BELL MAINTENANCE HOLE	○ BELL MH
EXISTING BELL POLE	○ BP
EXISTING HYDRO POLE	○ HP
EXISTING HYDRO GUY WIRE	—
PROPOSED LIGHT STANDARD	• LS
EXISTING DECIDUOUS TREE	—
EXISTING CONIFEROUS TREE	—
EXISTING SANITARY MAINTENANCE HOLE/NUMBER	○ SAN MH#
PROPOSED SANITARY MAINTENANCE HOLE/NUMBER	● SANMH#
EXISTING HYDRANT AND VALVE	◆ HYD & WV
PROPOSED HYDRANT AND VALVE	◆ HYD & WV
EXISTING WATER VALVE	◇ WV
PROPOSED WATER VALVE	◆ WV
PROPOSED CURB STOP VALVE	◆ CSV
EXISTING STORM MAINTENANCE HOLE	○ STM MH
EXISTING CATCH BASIN	□ CBMH #
TACTILE SURFACE INDICATORS	⊠
TRANSFORMER AND GROUNDING RODS	⊠
SWITCHGEAR	⊠
LIGHTING PEDESTAL	⊠
STOP SIGN	⊠



KEY PLAN

# GREENTREE GARDENS & EMPORIUM



TEMPORARY TOPSOIL STORAGE LOCATION  
 MAX HEIGHT 4.5m  
 MAX SIDE SLOPE 2:1  
 IF LEFT LONGER THAN 30 DAYS, VEGETATE WITH HYDROSEED AND MULCH

9.0m X 4.5m EXCAVATED SEDIMENT TRAP PER OPSD 219.220  
 CATCHMENT AREA = 0.74ha  
 BOTTOM ELEV. = 177.75  
 TRAP VOLUME = 40.5m<sup>3</sup>  
 ROCK FLOW CHECK DAM PER OPSD 219.210

8.0m X 4.0m EXCAVATED SEDIMENT TRAP PER OPSD 219.220  
 CATCHMENT AREA = 0.55ha  
 BOTTOM ELEV. = 178.35  
 TRAP VOLUME = 32.0m<sup>3</sup>

ROCK FLOW CHECK DAM PER OPSD 219.210

TOWN APPROVAL

LEGEND	
PROPOSED STRAW BALE FLOW CHECK (AS PER OPSD 219.210)	SBFC
PROPOSED ROCK FLOW CHECK (AS PER OPSD 219.180)	RFCD
PROPOSED HEAVY DUTY SILT FENCE (AS PER NVCA BSD-23 DRAFT)	—□—□—
PROPOSED SWALE / DITCH	—0.5%—
EXISTING OVERLAND FLOW	→

**DISCLAIMER AND COPYRIGHT**  
 CONTRACTOR MUST VERIFY ALL DIMENSIONS AND BE RESPONSIBLE FOR SAME. ANY DISCREPANCIES MUST BE REPORTED TO THE ENGINEER BEFORE COMMENCING WORK. DRAWINGS ARE NOT TO BE SCALED.  
 TATHAM ENGINEERING LIMITED CLAIMS COPYRIGHT TO THIS DRAWING WHICH MAY NOT BE USED FOR ANY PURPOSE OTHER THAN THAT PROVIDED IN THE CONTRACT BETWEEN THE OWNER/CLIENT AND THE ENGINEER WITHOUT THE EXPRESS CONSENT OF TATHAM ENGINEERING LIMITED.

**BENCHMARKS**  
 ELEVATIONS SHOWN ON THIS PLAN ARE RELATED TO GEODETIC DATUM AND ARE DERIVED FROM BENCH MARK No. 0011972U311 HAVING A PUBLISHED ELEVATION OF 181.032 METRES.

**NOTES**  
 LEGAL SURVEY INFORMATION AND LOT DIMENSIONS SHOWN ON THIS PLAN ARE TAKEN FROM A SURVEY PLAN PREPARED BY PATTEN & THOMSEN LTD, DATED, JANUARY 2, 2012 JOB No. 66-170-6  
 TOPOGRAPHIC SURVEY COMPLETED BY TATHAM ENGINEERING OCTOBER, 2022.





No.	REVISION DESCRIPTION	DATE
1.	1ST SUBMISSION	03/22
2.	2ND SUBMISSION	12/22
3.	3RD SUBMISSION	07/23
4.	4TH SUBMISSION	12/23
5.	5TH SUBMISSION	03/24

ENGINEER STAMP

**CRANBERRY MARSH ESTATES**  
 TOWN OF COLLINGWOOD  
**EROSION AND SEDIMENT CONTROL PLAN**



**TATHAM ENGINEERING**

DESIGN: KG	FILE: 120181	DWG: <b>ESC-1</b>
DRAWN: KB/SBU/AP	DATE: MAR 2022	
CHECK: DC	SCALE: 1:500	



**NOTES**

1. ALL SEDIMENT AND EROSION CONTROL MEASURES SHALL BE INSTALLED PRIOR TO THE COMMENCEMENT OF CONSTRUCTION. SEDIMENT AND EROSION CONTROL MEASURES THAT ARE DESIGNED TO CONTROL RUNOFF FROM SPECIFIC AREAS MUST BE INSTALLED PRIOR TO ANY DISTURBANCE OF THAT PART OF THE SITE. THE LOCATION OF ALL SILTATION AND EROSION CONTROL WORKS TO BE REVIEWED ON SITE AND MAY BE REVISED AS DIRECTED BY THE ENGINEER.
2. THE CONTRACTOR MAY CONSIDER ALTERNATIVE SEDIMENT AND EROSION CONTROL MEASURES. SUCH MEASURES MUST BE PRESENTED IN WRITING TO THE ENGINEER FOR APPROVAL OF THE TOWN AND NOTTAWASAGA VALLEY CONSERVATION AUTHORITY.
3. THE CONTRACTOR SHALL HAVE MATERIALS AVAILABLE ON SITE TO REPAIR SEDIMENT AND EROSION CONTROL MEASURES IN THE EVENT OF UNFORESEEN CONDITIONS SUCH AS HIGH WATER, EXTREME RAINFALL EVENTS, ETC.
4. ALL EROSION AND SEDIMENT CONTROL MEASURES MUST BE INSPECTED, CLEANED AND MAINTAINED BY THE CONTRACTOR AFTER EACH STORM EVENT. ALL WORKS WILL BE INSPECTED BY THE ENGINEER BI-WEEKLY AND AFTER EACH MAJOR STORM EVENT.
5. CONSTRUCTION OF ALL SILTATION AND EROSION CONTROL WORK IS TO BE IN ACCORDANCE WITH THE FOLLOWING STEPS:
  - 5.1. INSTALL NEW OR MAINTAIN EXISTING STONE MUD MAT AS PER DETAIL.
  - 5.2. INSTALL SILT FENCE AS PER NVCA STANDARDS (BSD-23).
  - 5.3. INSTALL TEMPORARY CATCH BASIN SEDIMENT TRAPS ON ALL NEW AND EXISTING CATCH BASINS. SEDIMENT TRAPS TO BE RECTANGULAR BY LAYFIELD OR APPROVED EQUAL. ALL CATCH BASINS TO REMAIN SCREENED UNTIL BASE COURSE ASPHALT IS PLACED AND LOT GRADING IS COMPLETE.
6. ALL CONSTRUCTION VEHICLES TO ACCESS SITE USING THE DESIGNATED CONSTRUCTION ACCESS POINTS.
7. EROSION AND SEDIMENT CONTROL MEASURES TO BE REMOVED BY THE CONTRACTOR ONCE GROUND COVER IS ESTABLISHED AND LANDSCAPING IS COMPLETE AND APPROVED BY THE ENGINEER.
8. STOCKPILE LOCATIONS ARE TO BE APPROVED BY THE ENGINEER.
9. PROVIDE FENCE OR APPROVED EQUAL ACROSS ALL CONSTRUCTION ACCESSES DURING PERIODS OF INACTIVITY.
10. CONSTRUCTION AREAS THAT EXCEED 30 DAYS OF INACTIVITY SHALL BE STABILIZED BY SEEDING IN ACCORDANCE WITH THE NOTTAWASAGA VALLEY CONSERVATION AUTHORITY'S TECHNICAL DESIGN GUIDELINES, STANDARDS AND POLICIES FOR SILTATION AND EROSION CONTROL. CONSTRUCTION CONTROL REQUIREMENTS, NOTES 1, 2 AND 3 AND/OR AS DIRECTED BY THE TOWN. THIS IS TO INCLUDE STOCKPILES OF FILL AND TOPSOIL.



TOWN APPROVAL

**DISCLAIMER AND COPYRIGHT**  
 CONTRACTOR MUST VERIFY ALL DIMENSIONS AND BE RESPONSIBLE FOR SAME. ANY DISCREPANCIES MUST BE REPORTED TO THE ENGINEER BEFORE COMMENCING WORK. DRAWINGS ARE NOT TO BE SCALED.  
 TATHAM ENGINEERING LIMITED CLAIMS COPYRIGHT TO THIS DRAWING WHICH MAY NOT BE USED FOR ANY PURPOSE OTHER THAN THAT PROVIDED IN THE CONTRACT BETWEEN THE OWNER/CLIENT AND THE ENGINEER WITHOUT THE EXPRESS CONSENT OF TATHAM ENGINEERING LIMITED.

**BENCHMARKS**  
 ELEVATIONS SHOWN ON THIS PLAN ARE RELATED TO GEODETIC DATUM AND ARE DERIVED FROM BENCH MARK No. 0011972U311 HAVING A PUBLISHED ELEVATION OF 161.032 METRES.

**NOTES**  
 LEGAL SURVEY INFORMATION AND LOT DIMENSIONS SHOWN ON THIS PLAN ARE TAKEN FROM A SURVEY PLAN PREPARED BY PATTEN & THOMSEN LTD, DATED, JANUARY 2, 2012 JOB No. 66-170-6  
 TOPOGRAPHIC SURVEY COMPLETED BY TATHAM ENGINEERING OCTOBER, 2022.

No.	REVISION DESCRIPTION	DATE	ENGINEER STAMP
1.	1ST SUBMISSION	03/22	
2.	2ND SUBMISSION	12/22	
3.	3RD SUBMISSION	07/23	
4.	4TH SUBMISSION	12/23	
5.	5TH SUBMISSION	03/24	


**CRANBERRY MARSH ESTATES**  
**TOWN OF COLLINGWOOD**

**EROSION AND SEDIMENT CONTROL DETAILS**


DESIGN: KG  
 FILE: 120181  
 DRAWN: KH/SBU/AP  
 DATE: MAR 2022  
 CHECK: DC  
 SCALE: N.T.S.

**TATHAM ENGINEERING**


**ESC-2**



KEY PLAN



GREENTREE GARDENS  
& EMPORIUM  
TATHAM ENGINEERING FILE 120234



**LEGEND**

- SANITARY AREA BOUNDARY (dashed line)
- AREA IDENTIFICATION NUMBER (circle with '101')
- AREA IN HECTARES (circle with '0.25 7.2')
- POPULATION BASED ON 2.4 PERSONS PER UNIT

TOWN APPROVAL

**DISCLAIMER AND COPYRIGHT**  
CONTRACTOR MUST VERIFY ALL DIMENSIONS AND BE RESPONSIBLE FOR SAME. ANY DISCREPANCIES MUST BE REPORTED TO THE ENGINEER BEFORE COMMENCING WORK. DRAWINGS ARE NOT TO BE SCALED.  
TATHAM ENGINEERING LIMITED CLAIMS COPYRIGHT TO THIS DRAWING WHICH MAY NOT BE USED FOR ANY PURPOSE OTHER THAN THAT PROVIDED IN THE CONTRACT BETWEEN THE OWNER/CLIENT AND THE ENGINEER WITHOUT THE EXPRESS CONSENT OF TATHAM ENGINEERING LIMITED.

**BENCHMARKS**  
ELEVATIONS SHOWN ON THIS PLAN ARE RELATED TO GEODETIC DATUM AND ARE DERIVED FROM BENCH MARK No. 0011972U311 HAVING A PUBLISHED ELEVATION OF 181.032 METRES.

**NOTES**  
LEGAL SURVEY INFORMATION AND LOT DIMENSIONS SHOWN ON THIS PLAN ARE TAKEN FROM A SURVEY PLAN PREPARED BY PATTEN & THOMSEN LTD, DATED, JANUARY 2, 2012 JOB No. 66-170-6  
TOPOGRAPHIC SURVEY COMPLETED BY TATHAM ENGINEERING OCTOBER, 2022.

No.	REVISION DESCRIPTION	DATE
1.	1ST SUBMISSION	03/22
2.	2ND SUBMISSION	12/22
3.	3RD SUBMISSION	07/23
4.	4TH SUBMISSION	12/23
5.	5TH SUBMISSION	03/24

ENGINEER STAMP

**CRANBERRY MARSH ESTATES**  
TOWN OF COLLINGWOOD

**SANITARY DRAINAGE PLAN**

**TATHAM ENGINEERING**

DESIGN: KG	FILE: 120181	DWG:
DRAWN: KH/SBU/AP	DATE: NOV 2021	<b>SAN-1</b>
CHECK: DC	SCALE: 1:500	

**LEGEND**

AREA BOUNDARY

AREA IDENTIFICATION NUMBER


AREA IN HECTARES

RUNOFF COEFFICIENT

EXISTING MAJOR OVERLAND FLOW DIRECTION

EXISTING DITCH FLOW DIRECTION

TOWN APPROVAL



KEY PLAN



**DISCLAIMER AND COPYRIGHT**  
 CONTRACTOR MUST VERIFY ALL DIMENSIONS AND BE RESPONSIBLE FOR SAME. ANY DISCREPANCIES MUST BE REPORTED TO THE ENGINEER BEFORE COMMENCING WORK. DRAWINGS ARE NOT TO BE SCALED.  
 TATHAM ENGINEERING LIMITED CLAIMS COPYRIGHT TO THIS DRAWING WHICH MAY NOT BE USED FOR ANY PURPOSE OTHER THAN THAT PROVIDED IN THE CONTRACT BETWEEN THE OWNER/CLIENT AND THE ENGINEER WITHOUT THE EXPRESS CONSENT OF TATHAM ENGINEERING LIMITED.

**BENCHMARKS**  
 ELEVATIONS SHOWN ON THIS PLAN ARE RELATED TO GEODETIC DATUM AND ARE DERIVED FROM BENCH MARK No. 0011972U311 HAVING A PUBLISHED ELEVATION OF 181.032 METRES.

**NOTES**  
 LEGAL SURVEY INFORMATION AND LOT DIMENSIONS SHOWN ON THIS PLAN ARE TAKEN FROM A SURVEY PLAN PREPARED BY PATTEN & THOMSEN LTD, DATED, JANUARY 2, 2012 JOB No. 66-170-6  
 TOPOGRAPHIC SURVEY COMPLETED BY TATHAM ENGINEERING OCTOBER, 2022.

No.	REVISION DESCRIPTION	DATE
1.	1ST SUBMISSION	03/22
2.	2ND SUBMISSION	12/22
3.	3RD SUBMISSION	07/23
4.	4TH SUBMISSION	12/23
5.	5TH SUBMISSION	03/24

ENGINEER STAMP


**CRANBERRY MARSH ESTATES**  
**TOWN OF COLLINGWOOD**

**PRE-DEVELOPMENT DRAINAGE PLAN**

**TATHAM ENGINEERING**

DESIGN: KG      FILE: 120181      DWG: **DP-1**  
 DRAWN: KH/SBU/AP      DATE: DEC 2021  
 CHECK: DC      SCALE: 1:500


LEGEND	
AREA BOUNDARY	
AREA IDENTIFICATION NUMBER	
AREA IN HECTARES	1.40 65%
CN VALUE/PERCENT IMPERVIOUS	
PROPOSED MAJOR OVERLAND FLOW DIRECTION	
EXISTING MAJOR OVERLAND FLOW DIRECTION	
PROPOSED FLOW DIRECTION	



KEY PLAN

GREENTREE GARDENS  
& EMPORIUM

TOWN APPROVAL



GEORGAIN BAY HOTEL

**DISCLAIMER AND COPYRIGHT**  
 CONTRACTOR MUST VERIFY ALL DIMENSIONS AND BE RESPONSIBLE FOR SAME. ANY DISCREPANCIES MUST BE REPORTED TO THE ENGINEER BEFORE COMMENCING WORK. DRAWINGS ARE NOT TO BE SCALED.  
 TATHAM ENGINEERING LIMITED CLAIMS COPYRIGHT TO THIS DRAWING WHICH MAY NOT BE USED FOR ANY PURPOSE OTHER THAN THAT PROVIDED IN THE CONTRACT BETWEEN THE OWNER/CLIENT AND THE ENGINEER WITHOUT THE EXPRESS CONSENT OF TATHAM ENGINEERING LIMITED.

**BENCHMARKS**  
 ELEVATIONS SHOWN ON THIS PLAN ARE RELATED TO GEODETIC DATUM AND ARE DERIVED FROM BENCH MARK No. 0011972U311 HAVING A PUBLISHED ELEVATION OF 181.032 METRES.



**NOTES**  
 LEGAL SURVEY INFORMATION AND LOT DIMENSIONS SHOWN ON THIS PLAN ARE TAKEN FROM A SURVEY PLAN PREPARED BY PATTEN & THOMSEN LTD, DATED, JANUARY 2, 2012 JOB No. 66-170-6  
 TOPOGRAPHIC SURVEY COMPLETED BY TATHAM ENGINEERING OCTOBER, 2022.

No.	REVISION DESCRIPTION	DATE
2.	2ND SUBMISSION	12/22
3.	UPDATE TO IMPERVIOUS VALUES	01/23
4.	3RD SUBMISSION	07/23
5.	4TH SUBMISSION	12/23
6.	5TH SUBMISSION	03/24

ENGINEER STAMP

**CRANBERRY MARSH ESTATES**  
**TOWN OF COLLINGWOOD**  
 POST-DEVELOPMENT  
 DRAINAGE PLAN

		DESIGN: KG	FILE: 120181	DWG:
		DRAWN: KH/SBU/AP	DATE: FEB 2022	<b>DP-2</b>
CHECK: DC	SCALE: 1:500			



**DISCLAIMER AND COPYRIGHT**

CONTRACTOR MUST VERIFY ALL DIMENSIONS AND BE RESPONSIBLE FOR SAME. ANY DISCREPANCIES MUST BE REPORTED TO THE ENGINEER BEFORE COMMENCING WORK. DRAWINGS ARE NOT TO BE SCALED.

TATHAM ENGINEERING LIMITED CLAIMS COPYRIGHT TO THIS DRAWING WHICH MAY NOT BE USED FOR ANY PURPOSE OTHER THAN THAT PROVIDED IN THE CONTRACT BETWEEN THE OWNER/CLIENT AND THE ENGINEER WITHOUT THE EXPRESS CONSENT OF TATHAM ENGINEERING LIMITED.

**BENCHMARKS**

ELEVATIONS SHOWN ON THIS PLAN ARE RELATED TO GEODETIC DATUM AND ARE DERIVED FROM BENCH MARK No. 0011972U311 HAVING A PUBLISHED ELEVATION OF 181.032 METRES.

**NOTES**

LEGAL SURVEY INFORMATION AND LOT DIMENSIONS SHOWN ON THIS PLAN ARE TAKEN FROM A SURVEY PLAN PREPARED BY PATTEN & THOMSEN LTD. DATED, JANUARY 2, 2012 JOB No. 66-170-6

TOPOGRAPHIC SURVEY COMPLETED BY TATHAM ENGINEERING OCTOBER, 2022.

No.	REVISION DESCRIPTION	DATE
1.	1ST SUBMISSION	03/22
2.	2ND SUBMISSION	12/22
3.	3RD SUBMISSION	07/23
4.	4TH SUBMISSION	12/23
5.	5TH SUBMISSION	03/24

**ENGINEER STAMP**

D. M. CASULLO  
LICENSED PROFESSIONAL ENGINEER  
2024 03 22  
PROVINCE OF ONTARIO

**CRANBERRY MARSH ESTATES**  
TOWN OF COLLINGWOOD



**SITE SERVICING PLAN AND PROFILE**

**TATHAM ENGINEERING**


DESIGN: KG  
DRAWN: KH/SBU/AP  
CHECK: DC

FILE: 120181  
DATE: MAR 2022  
SCALE: H-1:500  
V-1:50

DWG: **PP-1**



KEY PLAN



**DISCLAIMER AND COPYRIGHT**  
 CONTRACTOR MUST VERIFY ALL DIMENSIONS AND BE RESPONSIBLE FOR SAME. ANY DISCREPANCIES MUST BE REPORTED TO THE ENGINEER BEFORE COMMENCING WORK. DRAWINGS ARE NOT TO BE SCALED.  
 TATHAM ENGINEERING LIMITED CLAIMS COPYRIGHT TO THIS DRAWING WHICH MAY NOT BE USED FOR ANY PURPOSE OTHER THAN THAT PROVIDED IN THE CONTRACT BETWEEN THE OWNER/CLIENT AND THE ENGINEER WITHOUT THE EXPRESS CONSENT OF TATHAM ENGINEERING LIMITED.

**BENCHMARKS**  
 ELEVATIONS SHOWN ON THIS PLAN ARE RELATED TO GEODETIC DATUM AND ARE DERIVED FROM BENCH MARK No. 00119720311 HAVING A PUBLISHED ELEVATION OF 181.032 METRES.

**NOTES**  
 LEGAL SURVEY INFORMATION AND LOT DIMENSIONS SHOWN ON THIS PLAN ARE TAKEN FROM A SURVEY PLAN PREPARED BY PATTEN & THOMSEN LTD, DATED, JANUARY 2, 2012 JOB No. 56-170-6  
 TOPOGRAPHIC SURVEY COMPLETED BY TATHAM ENGINEERING OCTOBER, 2022.


No.	REVISION DESCRIPTION	DATE
1.	1ST SUBMISSION	03/22
2.	2ND SUBMISSION	12/22
3.	3RD SUBMISSION	07/23
4.	4TH SUBMISSION	12/23
5.	5TH SUBMISSION	03/24

**ENGINEER STAMP**  
 LICENSED PROFESSIONAL ENGINEER  
 2024.03.22  
 D. M. CASULLA  
 PROVINCE OF ONTARIO

**CRANBERRY MARSH ESTATES**  
 TOWN OF COLLINGWOOD  
 SITE GRADING PLAN

**TATHAM ENGINEERING**  
 DESIGN: KH FILE: 120181 DWG:  
 DRAWN: KH/SBU/AP DATE: OCT 2021 **SG-1**  
 CHECK: DC SCALE: AS NOTED





- GENERAL - CONSTRUCTION**
- ALL WORK TO BE CARRIED OUT IN ACCORDANCE WITH TOWN OF COLLINGWOOD STANDARDS, O.P.S.D. AND O.P.S.S. WHERE CONFLICT OCCURS, TOWN OF COLLINGWOOD STANDARD TO GOVERN.
  - TRENCH BACKFILL TO OPSS 802.010 TO BE SELECT NATIVE MATERIAL OR IMPORTED SELECT SUBGRADE TO OPSS 1010. BACKFILL TO BE PLACED IN MAXIMUM 200 mm THICK LIFTS AND COMPACTED TO 95% OF THE MATERIAL'S STANDARD PROCTOR MAXIMUM DRY DENSITY (SPMDD).
  - PIPE BEDDING TO BE GRANULAR 'A' PIPE COVER TO BE GRANULAR 'B' MAX. AGGREGATE SIZE 25mm FOR RIGID PIPE AND GRANULAR 'A' FOR FLEXIBLE PIPE. (MINIMUM BEDDING DEPTH 150 mm, MINIMUM COVER 300mm, COMPACTED TO A MINIMUM 95% SPMDD).
  - CLEAR STONE WRAPPED IN FILTER FABRIC CAN BE SUBSTITUTED FOR EMBEDMENT MATERIAL IF APPROVED BY THE ENGINEER.
  - ALL TOPSOIL AND EARTH EXCAVATION TO BE STOCK PILED OR REMOVED TO OPSS 180. MANAGEMENT AND DISPOSAL OF EXCESS MATERIAL TO AN APPROVED SITE AS DIRECTED BY ENGINEER.
  - THE OWNER'S ENGINEER SHALL PROVIDE BENCH MARK ELEVATIONS AND HORIZONTAL ALIGNMENT REFERENCE FOR THE CONTRACTOR. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE DETAILED LAYOUT OF THE WORK.
  - ALL PROPERTY BARS TO BE PRESERVED AND REPLACED BY O.L.S. AT CONTRACTOR'S EXPENSE IF REMOVED DURING CONSTRUCTION.
  - ALL MAINTENANCE HOLE AND CATCHBASIN FRAMES AND COVERS TO BE SET TO BASE COURSE H/L3 ASPHALT ELEVATION AND RAISED PRIOR TO PLACEMENT OF FINAL COURSE H/L3 ASPHALT.
  - THE CONTRACTOR SHALL MAKE HIS OWN ARRANGEMENTS FOR THE SUPPLY OF TEMPORARY WATER AND POWER.
  - DEWATERING TO BE CARRIED OUT IN ACCORDANCE WITH OPSS-517 AND 518 TO MAINTAIN ALL TRENCHES IN A DRY CONDITION.
  - ALL ENGINE DRIVEN PUMPS TO BE ADEQUATELY SILENCED, SUITABLE FOR OPERATION IN A RESIDENTIAL DISTRICT.
  - ALL DISTURBED AREAS TO BE REINSTATED TO PREVIOUS CONDITION OR BETTER.
  - THE CONTRACTOR IS RESPONSIBLE FOR PRESERVATION OF ALL EXISTING FACILITIES AS WELL AS NOTIFYING ALL UTILITY COMPANIES PRIOR TO COMMENCING WORK AND CO-ORDINATE CONSTRUCTION ACCORDINGLY.
  - ALL SIGNAGE TO BE LAWFULLY ERECTED AND MAINTAINED IN ACCORDANCE TO THE TOWN SIGN BY-LAW.
  - CLEARING, GRUBBING AND REMOVAL OF SURFACE BOULDERS TO OPSS 201.
  - GRADING TO OPSS 206.
  - COMPACTING TO OPSS 501.
  - DUST SUPPRESSANTS TO OPSS 506.
  - TREE REMOVALS AND/OR TRANSPLANTS TO BE COMPLETED OUTSIDE OF MIGRATORY BIRDS NESTING SEASON FROM APRIL 1<sup>ST</sup> TO AUGUST 31<sup>ST</sup>. REMOVALS MAY TAKE PLACE DURING THIS RESTRICTED TIME ONLY IF THE REQUIREMENTS OF MIGRATING BIRDS CONVENTION ACT ARE MET AND NESTING ACTIVITY IS ROUTINELY MONITORED BY QUALIFIED INDIVIDUALS (I.E. WILDLIFE BIOLOGIST).

- SANITARY SEWERS**
- MAINTENANCE HOLES TO OPSS 701.010 AND 701.030.
  - BENCHING TO OPSS - 701.021.
  - STEPS TO OPSS - 405.010.
  - FROST STRAPS SHALL BE INSTALLED ON ALL MAINTENANCE HOLE AS PER OPSS - 701.100.
  - FRAMES AND COVERS TO OPSS - 401.030 (WATER TIGHT COVER).
  - PIPE SUPPORT AT MAINTENANCE HOLES AS PER OPSS 708.020.
  - ALL MAINTENANCE HOLES, UNLESS EXPRESSLY IDENTIFIED ARE 1200 mm DIAMETER WITH WATER TIGHT INSERTS.
  - GENERAL INSTALLATION AND TESTING OF SEWERS AND APPURTENANCES TO BE IN ACCORDANCE WITH O.P.S.S. 407, 408, 409 (CCTV), 410, 421 AND ALL SPECIFICATIONS REFERENCED WITHIN THESE SECTIONS.
  - SERVICE CONNECTIONS TO BE 125 mm DIA., TERMINATED WHERE SPECIFIED ON THE DRAWING COMPLETE WITH PLUG AND MARKED WITH A 38mm X 89mm POST PAINTED GREEN FROM THE INVERT OF THE SERVICE TO 600 mm ABOVE GRADE.
  - SERVICE CONNECTION TO OPSS 1006.020, GRANULAR A BEDDING AND EMBEDMENT.
  - RIGID BOARD INSULATION (HI-40) REQUIRED FOR FROST PROTECTION OF SEWER WITH LESS THAN 1.2 m MINIMUM COVER. INSULATION TO BE MINIMUM 50 mm THICK AND HAVE A MINIMUM WIDTH OF 1.2m.






- WATER MAINS**
- THRUST BLOCKS TO OPSS-1103.010 AND 1103.020 WHERE SUITABLE SOILS ARE ENCOUNTERED.
  - MINIMUM COVER ON WATER MAIN SERVICES TO BE 1.7 m.
  - GATE VALVES, BENDS AND FITTINGS TO BE CONNECTED WITH ROMAC GRIP RING RESTRAINING CLAMP.
  - CLEARANCE BETWEEN WATER MAINS AND SEWERS TO BE A MINIMUM OF 0.5m VERTICAL WHERE WATER MAIN IS BELOW SEWER OR 2.5m MINIMUM HORIZONTAL SEPARATION. WHERE WATER MAIN IS ABOVE SEWER, THE MINIMUM SEPARATION TO BE 150 mm (BEDDING MATERIAL).
  - GENERAL INSTALLATION AND TESTING OF WATER MAIN AND APPURTENANCES TO BE IN ACCORDANCE WITH O.P.S.S. 701 AND ALL SPECIFICATIONS REFERENCED WITHIN THESE SECTIONS.
  - ALL WORK ON TOWN PROPERTY AND ON TOWN OF COLLINGWOOD WATER DEPARTMENT (TCWD) WATER MAINS MUST BE UNDERTAKEN BY TCWD OR AN APPROVED CONTRACTOR WITH TCWD INSPECTION, ALL AT DEVELOPER'S COST.
  - SERVICE CONNECTIONS TO OPSS-1104.010, 100 mm GRANULAR 'A' EMBEDMENT AND COVER OVER PIPE. TERMINATE WHERE SPECIFIED ON DRAWING C/W CURB STOP AND BOX, TESTING TAIL TO SURFACE ATTACHED TO A 38mm x 89mm MARKER POST PAINTED BLUE FROM THE INVERT OF THE SERVICE TO 600 mm ABOVE GRADE. (I) ALL SERVICES ARE TO BE CONSTRUCTED IN ACCORDANCE WITH TOWN STANDARDS.
  - WATER MAIN SERVICES - 20mm TYPE K COPPER, MAIN STOPS TO 201-3343, 3/4", BALL STYLE, AWWA THREAD BY COMPRESSION CAMBRIDGE BRASS. CURB STOPS TO 203-3343, 3/4" BALL STYLE WITH DRAIN, COMPRESSION JOINT CAMBRIDGE BRASS. SERVICE BOXES TO NUMBER 7, D-1 CLOW OR MUELLER WITH 24" BLACK RODS STRAIGHT OR OTHERWISE NOTED ON DRAWINGS.
  - ALL WATER TESTING AND WATER MAIN CHLORINATION WILL BE CONDUCTED BY TCWD AT THE DEVELOPER'S COST. WATER MAINS ARE NOT TO BE CONNECTED TO THE EXISTING WATER MAINS UNTIL BACTERIOLOGICAL TESTING HAS BEEN SUCCESSFULLY COMPLETED. NEW WATER MAINS CAN NOT BE CONNECTED TO EXISTING MAINS UNTIL THEY HAVE PASSED BACTERIOLOGICAL TESTING AND AS SUCH A TEMPORARY BACKFLOW PREVENTOR WILL NEED TO BE INSTALLED BETWEEN THE LIVE TAP AND THE NEW SERVICE TO FACILITATE ADEQUATE PROTECTION OF THE EXISTING WATER MAIN. IT SHOULD BE NOTED THAT THIS TESTING TAKES APPROXIMATELY A WEEK TO COMPLETE AND MUST BE CONDUCTED BY TCWD. A WORK PLAN FOR THIS WORK MUST BE SUBMITTED TO TCWD FOR APPROVAL.
  - AS A GENERAL PRINCIPLE EACH PROPERTY SHALL HAVE ONE SERVICE AND ONE METER.
  - NO WATER VALVES ARE TO BE OPERATED WITHOUT TCWD APPROVAL.

- STORM SEWERS**
- CATCH BASINS AND DOUBLE CATCH BASINS TO OPSS 705.010 AND 705.020 C/W 600 mm SUMP. REAR LOT CATCH BASIN AND DITCH INLET CATCH BASINS TO OPSS 705.010 WITHOUT SUMP.
  - CATCH BASINS AND DOUBLE CATCH BASINS FRAMES AND GRATES TO OPSS 400.020. REAR LOT CATCH BASIN FRAMES AND GRATES TO OPSS 400.120.
  - CATCH BASIN LEADS - 250 mm DIA. SINGLE AND 300 mm DIA. DOUBLE. CATCH BASIN CONNECTIONS TO OPSS 708.010 AND OPSS 708.030.
  - PIPE SUPPORT AT GRATES TO OPSS 708.020. CATCH BASINS AND INLET STRUCTURES FITTED WITH SEDIMENT TRAPS DURING CONSTRUCTION AND CLEANED OUT AS REQUIRED PRIOR TO ASSUMPTION OF THE WORK.
  - HEADWALLS TO BE INSTALLED IN ACCORDANCE WITH OPSS 804.030 (PIPE LESS THAN 900 mm DIA.) OR OPSS 804.040 (AS SPECIFIED), C/W GRATING IN ACCORDANCE WITH OPSS 804.050.

- ROAD AND PARKING**
- SUBGRADE AND ALL GRANULAR 'A' BOULEVARD MATERIAL TO BE COMPACTED TO A MINIMUM DRY DENSITY OF AT LEAST 95% SPMDD. SUBGRADE TO BE PROOF ROLLED AND CERTIFIED PRIOR TO PLACING GRANULAR 'B'.
  - GRANULAR 'A' AND 'B' BASE TO BE COMPACTED TO 100% OF THE MATERIAL'S RESPECTIVE SPMDD.
  - LIGHT DUTY PAVEMENT TWO LIFTS TOTAL 90mm (50mm H/LB AND 40mm H/L3), 150mm GRANULAR 'A', 300mm GRANULAR 'B'. HEAVY DUTY PAVEMENT TWO LIFTS TOTAL 120mm (80mm H/LB AND 40mm H/L3), 150 mm GRANULAR 'A', 450mm GRANULAR 'B', ALL SUBDRAINS TO BE CONSTRUCTED IN ACCORDANCE WITH OPSS 405.
  - CONCRETE SEMI-MOUNTABLE CURB WITH STANDARD GUTTER TO OPSS 600.060 INCLUDING SUPERELEVATED. CONCRETE BARRIER CURB WITH STANDARD GUTTER TO OPSS 600.040. CONCRETE BARRIER CURB TO OPSS 600.110.
  - SELECT SUBGRADE MATERIAL, OR IMPORTED GRANULAR MATERIAL APPROVED BY THE ENGINEER, COMPACTED TO 98% S.P.M.D.D. TO BE USED AS FILL IN ALL AREAS WHERE PROPOSED PIPE INVERTS ARE HIGHER THAN EXISTING GRADE OR AS INSTRUCTED BY THE ENGINEER.
  - ALL GRANULARS AND ASPHALT MATERIALS AND PLACEMENT TO BE IN ACCORDANCE WITH OPSS 314 AND OPSS 310.
  - JOINTS WITH EXISTING ASPHALT TO BE SAW CUT STRAIGHT PRIOR TO PLACING NEW ASPHALT AND TACK COAT APPLIED TO EXISTING ASPHALT. ASPHALT JOINT WITH HIGHWAY No. 26 TO BE COMPLETE WITH LAP JOINT, SEE DETAIL THIS PAGE.
  - REINSTATEMENT OF ALL DISTURBED BOULEVARD TO INCLUDE REGRADING, MINIMUM 150mm TOPSOIL AND SOD TO OPSS.MUNI 802 AND 803.
  - ALL FIRE ROAD SIGNAGE TO BE AS PER TOWN OF COLLINGWOOD BY-LAW 96-37.
  - ENTRANCE AS PER OPSS 350.010, SIDEWALKS TO OPSS 310.050 AND 310.010.
  - SIDEWALKS SHALL BE COMPLETE WITH TACTILE WALKING SURFACE INDICATOR STRIPS, INSTALLED AS PER OPSS 310.039 AND OPSS.MUNI 351.

- MATERIALS**
- SANITARY SEWER SDR-35 PVC, SANITARY SERVICES - SDR 28 PVC
  - SANITARY MAIN - DUCTILE IRON CLASS 52, OR PRESSURE CLASS 350 CEMENT LINED. CONDUCTIVITY CONNECTORS TO BE USED ON ALL JOINTS.
  - WATER SERVICE CONNECTIONS TO BE TYPE 'K' COPPER PIPE.
  - VALVES - RESILIENT SEATED, RSGV, MECHANICAL JOINT, OPEN LEFT CLOW OR MUELLER WITH 5 SL-48 SLIDING VALVE BOX, TO AWWA C504.
  - MECHANICAL JOINT DUCTILE FITTINGS - AWWA/ANSI C153/A21.53.
  - RESTRAINER - ROMAC GRIPPER RING FOR PIPE SIZES UP TO 300 mm AND SIGMA ONE-LOCK FOR PIPE SIZES GREATER THAN 300 mm.
  - LIVE TAP SADDLES - EPOXY COATED C/W STAINLESS STEEL BOLTS.
  - LIVE TAP VALVE - RESILIENT SEATED RSGV, LIVE TAPE VALVE, OPEN LE.
  - FILTER FABRIC - TERRAFIX 270R OR APPROVED EQUAL.
  - PERFORATED SUBDRAINS - 100mm DIA. BIG 'O' WITH GEOTEXTILE FILTER SOCK OR APPROVED EQUAL UNLESS NOTED OTHERWISE.
  - ALL SPECIFIED AGGREGATES TO OPSS 1010.
  - INSULATION - STYROFOAM HI-40.
  - ALL HYDRANTS SHALL BE CANADA VALVE, CENTURY NO. 1 OPEN LEFT WITH 2 CSA HOSE PORTS, ONE STORZ 4" PUMPER PORT, AND A BREAK AWAY TYPE 6" MJ BASE.

TOWN APPROVAL



**DISCLAIMER AND COPYRIGHT**  
 CONTRACTOR MUST VERIFY ALL DIMENSIONS AND BE RESPONSIBLE FOR SAME. ANY DISCREPANCIES MUST BE REPORTED TO THE ENGINEER BEFORE COMMENCING WORK. DRAWINGS ARE NOT TO BE SCALED.  
 TATHAM ENGINEERING LIMITED CLAIMS COPYRIGHT TO THIS DRAWING WHICH MAY NOT BE USED FOR ANY PURPOSE OTHER THAN THAT PROVIDED IN THE CONTRACT BETWEEN THE OWNER/CLIENT AND THE ENGINEER WITHOUT THE EXPRESS CONSENT OF TATHAM ENGINEERING LIMITED.

**BENCHMARKS**  
 ELEVATIONS SHOWN ON THIS PLAN ARE RELATED TO GEODETIC DATUM AND ARE DERIVED FROM BENCH MARK No. 0011972U311 HAVING A PUBLISHED ELEVATION OF 181.032 METRES.


**NOTES**  
 LEGAL SURVEY INFORMATION AND LOT DIMENSIONS SHOWN ON THIS PLAN ARE TAKEN FROM A SURVEY PLAN PREPARED BY PATTEN & THOMSON LTD., DATED, JANUARY 2, 2012 JOB No. 66-170-6  
 TOPOGRAPHIC SURVEY COMPLETED BY TATHAM ENGINEERING OCTOBER, 2022.

No.	REVISION DESCRIPTION	DATE
1.	1ST SUBMISSION	03/22
2.	2ND SUBMISSION	12/22
3.	3RD SUBMISSION	07/23
4.	4TH SUBMISSION	12/23
5.	5TH SUBMISSION	03/24

ENGINEER STAMP

**CRANBERRY MARSH ESTATES**  
 TOWN OF COLLINGWOOD  
**DETAILS & NOTES**

**TATHAM ENGINEERING**  
 DESIGN: KG/SBU FILE: 120181 DWG:  
 DRAWN: KH/SBU DATE: NOV 2021 **DE-1**  
 CHECK: DC SCALE: 1:500



	PRIMARY CABLE DESCRIPTION	INSTALLATION
12	PC01: LOOP FEEDER: 1C#1/0 AWG CU CLASS B STRANDED, 15KV RATED, TRXLPE, 100% CONCENTRIC NEUTRAL, IN UNDERGROUND DUCTBANK, COMPLIES WITH CSA C68.3, LATEST ISSUE.	1-103mm $\phi$ TYPE DB2 DIRECT BURIED DUCT(S) WITH SAND BEDDING ALL AROUND.
12	PC02: 3C#4/0, AL, TYPE USE90, CLASS 'B' STRANDED, 600V RATED, 2-CONDUCTOR + 100% NEUTRAL, XLPE INSULATION PVC JACKET	1-103mm $\phi$ TYPE DB2 DIRECT BURIED DUCT(S) WITH SAND BEDDING ALL AROUND.

- SINGLE LINE DIAGRAM NOTES:**
- PC01: PRIMARY LOOP FEEDER CABLE: 1C#1/0AWG IN 103mm $\phi$  PVC DUCT. REFER TO EPCOR'S "GENERAL CONTRACTOR REQUIREMENTS AND MATERIAL SPECIFICATIONS" FOR PRIMARY CABLE SPECIFICATIONS.
  - 1-POSITION 200A RATED METER BASE: HYDEL ENTERPRISES EK400R0 SERIES, THOMAS AND BETTS MICROELECTRIC BS2-TCV, EATON CULTER-HAMMER LM2 120 AMP, LINE/LOAD CABLES UP TO 250MCM CU/AL, WEATHERPROOF RATED (EEMAC 3R). REFER TO EPCOR'S "GENERAL CONTRACTOR REQUIREMENTS AND MATERIAL SPECIFICATIONS".
  - EPCOR TO SUPPLY AND INSTALL NEW TRANSFORMER. CONTRACTOR TO PROVIDE CONCRETE VAULT AND GROUNDING GRID. PER EPCOR STANDARDS.
  - ALL PRIMARY AND SECONDARY CABLE TERMINATIONS INSIDE EACH TRANSFORMER AND AT HYDRO POLES WILL BE PERFORMED BY EPCOR.
  - EXPOSED SECTIONS OF CONDUIT (ABOVE GRADE) FOR SECONDARY FEEDER CABLES MUST BE RIGID PVC.
  - PC02: SECONDARY SERVICE CABLES FOR 1-POSITION 200A METER BASES: 3C#4/0AWG AL USE90. REFER TO EPCOR'S "GENERAL CONTRACTOR REQUIREMENTS AND MATERIAL SPECIFICATIONS" FOR SECONDARY CABLE SPECIFICATIONS.
  - TYPICAL FOR TOWNHOUSE UNITS WITH 200A SERVICE
  - MAXIMUM ELECTRICAL SERVICES TO EACH UNIT: 200AMP MAX., 120/240VAC, 1-PHASE, 60HZ. SERVICE CABLES TO ENTER UNIT (VIA UNDERGROUND) BY OTHERS DURING THIS CONTRACT. CONTRACTOR TO COORDINATE LOCATION OF METERS WITH CONTRACTOR INSTALLING UNIT PANELBOARDS PRIOR TO INSTALLING SERVICE CABLES TO METER BASES.
  - EPCOR TO RE-FRAME EXISTING EPO1 HYDRO POLE TO ACCOMMODATE NEW 1 $\phi$  PRIMARY RISER.
  - CONTRACTOR TO PROVIDE 20m OF ADDITIONAL PRIMARY CABLE AT BASE OF POLE, INCLUDES CONDUITS AND CABLE GUARDS AT POLE FOR PRIMARY RISER. EPCOR TO COMPLETE TERMINATIONS OF PRIMARY CABLES. ALL WORK TO BE DONE TO EPCOR'S STANDARDS.
  - TERMINATE SECONDARY ELECTRICAL SERVICE AT LOT LINE ON DRIVEWAY SIDE OF LOT PER EPCOR STANDARDS. SECURE 1m OF SECONDARY CABLE TO 2" X 4" X 8" WOOD MARKER STAKE. SECONDARY SPLICE AND CONNECTION TO METER BASE BY OTHERS. COORDINATE DRIVEWAY AND METER BASE LOCATIONS WITH DEVELOPER.
  - REFER TO EPCOR GENERAL CONTRACTOR INFORMATION, AS PROVIDED ON THEIR WEBPAGE: [www.epcor.com](http://www.epcor.com)


**1 SINGLE LINE DIAGRAM - 2400V**  
 E1.1 - EXCEPT FOR STREETLIGHT SYSTEM, ALL ELECTRICAL EQUIPMENT AND CABLES TO BE OWNED AND OPERATED BY EPCOR.

DISCLAIMER AND COPYRIGHT  
 CONTRACTOR MUST VERIFY ALL DIMENSIONS AND BE RESPONSIBLE FOR SAME. ANY DISCREPANCIES MUST BE REPORTED TO THE ENGINEER BEFORE COMMENCING WORK. DRAWINGS ARE NOT TO BE SCALED.  
 TATHAM ENGINEERING LIMITED CLAIMS COPYRIGHT TO THIS DRAWING WHICH MAY NOT BE USED FOR ANY PURPOSE OTHER THAN THAT PROVIDED IN THE CONTRACT BETWEEN THE OWNER/CLIENT AND THE ENGINEER WITHOUT THE EXPRESS CONSENT OF TATHAM ENGINEERING LIMITED.


**ACCEPTED FOR CONSTRUCTION EPCOR**

per .....

Date: .....




No.	REVISION DESCRIPTION	DATE
1.	1ST SUBMISSION	DEC 2022
2.	ISSUED TO EPCOR FOR REVIEW	MAR 2023
3.	2ND SUBMISSION	JULY 2023
4.	3RD SUBMISSION	DEC 2023



**CRANBERRY MARSH ESTATES**  
 TOWN OF COLLINGWOOD

SINGLE LINE DIAGRAM



		DESIGN: RJW	FILE: 120181	DWG:
		DRAWN: RJW	DATE: OCT 2021	<b>E1.1</b>
CHECK: SRT	SCALE: AS SHOWN			




**GENERAL NOTES - JOINT TRENCH**

- ① CLEAR UNDISTURBED SOIL OR 100mm SCREENED SAND BEDDING COMPACTED TO 98% STANDARD PROCTOR MATERIAL DRY DENSITY (SPMDD)
- ② PRIMARY SERVICE 103mm $\phi$  PVC TYPE DBII DUCT (TRANSFORMER SIDE) C/W CABLE. RED PHASE AT STREET SIDE, THEN WHITE PHASE, BLUE PHASE (ACCORDINGLY). UNUSED POSITIONS MAY BE USED AS SECONDARY SERVICE DUCTS.
- ③ CLEAR SCREENED COMPACTED SAND. MAINTAIN SEPARATION BETWEEN DUCTS BY USE OF PVC DUCT SPACERS TO MAINTAIN UNIFORM DUCT CLEARANCES.
- ④ TWO ROWS OF 103mm $\phi$  PVC TYPE DBII SECONDARY SERVICE DUCTS C/W USEI90 CABLES
- ⑤ OUTLINE OF TRENCH EXCAVATION. ALL TRENCHING TO BE IN CONFORMANCE WITH CONSTRUCTION SAFETY ASSOCIATION OF ONTARIO "TRENCHING SAFETY" GUIDELINES
- ⑥ GAS LINE; SIZE AND ROUTING BY GAS UTILITY. MAINTAIN MINIMUM 305mm CLEARANCE TO ALL ELECTRICAL EQUIPMENT, CABLES, PEDESTALS, GROUNDING RODS, WATER VALVES AND FIRE HYDRANTS
- ⑦ CLEAR SCREENED, FROST FREE, SAND BEDDING COMPACTED TO 98% SPMDD.
- ⑧ STREET LIGHTING SERVICE DUCTS 53mm $\phi$  PVC TYPE DBII DUCT(S). MINIMUM 600mm COVER.
- ⑨ CABLE TELEVISION AND TELEPHONE UTILITY SERVICE CABLES AND/OR DUCTS. MINIMUM 600mm COVER.
- ⑩ ELECTRICAL WARNING TAPE,  $\frac{1}{2}$  WAY BETWEEN TOP DUCTS AND GRADE
- ⑪ GAS LINE WARNING TAPE, AS REQUIRED BY UTILITY
- ⑫ UNDISTURBED SOIL OR ENGINEERED BACKFILL
- ⑬ COMPACTED FROST- AND DEBRIS- FREE NATIVE BACKFILL TO TOWN REQUIREMENTS, COMPACTED TO 98% SPMDD
- ⑭ TOPSOIL
- ⑮ NEW TOPPING AS SPECIFIED BY OTHERS
- ⑯ INSTALLATION REFERENCE POINT - CENTRE-LINE OF POWER UTILITY TRENCH


ALL ELECTRICAL POWER CABLE TO BE INSTALLED IN CONFORMANCE WITH EPCCOR STANDARDS AND LATEST EDITIONS OF ONTARIO ELECTRICAL SAFETY CODE AND CSA STANDARD CAN3-C22.3  
PROVIDE LARGE UTILITY "SWEEP" FITTINGS FOR ALL DUCT BENDS



**3 PEDESTAL SECONDARY DUCTBANK**  
- NTS, DIMENSIONS SHOWN IN MILLIMETRES (mm). DUCTBANK NOTES  
• GLUE ALL PVC JOINTS



**4 PROPOSED HYDRO POLE SKETCHES**




KEY PLAN

- NOTES:**
- ① USF STANDARD NUMBERS LISTED FOR REFERENCE ONLY. OTHER USF STANDARDS MAY APPLY TO THIS WORK.
  - ② SOILS TESTING HAS NOT BEEN CONDUCTED FOR THIS PROJECT. THE DESIGN OF THE ANCHORS IS BASED ON SOIL CLASSIFICATION 4 AS DESCRIBED IN USF TABLE 06-04. THE SOIL CLASSIFICATION IS TO BE CONFIRMED BY THE INSTALLER/CONTRACTOR DURING CONSTRUCTION. IF SOIL OF A DIFFERENT CLASSIFICATION IS ENCOUNTERED, THE INSTALLER MUST CONTACT TATHAM ENGINEERING LIMITED. FOR FURTHER DIRECTION/INVESTIGATION.
  - ③ TERMINATE SECONDARY DUCTS AND CABLES AT SAME OFFSET IN BOULEVARD AS THE SANITARY AND WATER SERVICES. PROVIDE 2"x4" WOOD MARKER POST FOR DEMARCATON POINT OF SECONDARY DUCTS AND CABLES. PROVIDE ADDITIONAL 1.0m OF CABLE ABOVE GRADE FOR FUTURE SPLICE AND FROST LOOP.
  - ④ CONTRACTOR TO COORDINATE FINAL METER BASE LOCATIONS WITH BUILDERS.

**2 JOINT TRENCH DETAIL WITH GAS - JOINT TRENCH PROFILE**


E2.1 - SCALE: NTS



**1 ELECTRICAL SITE PLAN - POWER LAYOUT**

E2.1 - SCALE 1:500

**STANDARD ELECTRICAL LEGEND**



**DISCLAIMER AND COPYRIGHT**  
CONTRACTOR MUST VERIFY ALL DIMENSIONS AND BE RESPONSIBLE FOR SAME. ANY DISCREPANCIES MUST BE REPORTED TO THE ENGINEER BEFORE COMMENCING WORK. DRAWINGS ARE NOT TO BE SCALED.


TATHAM ENGINEERING LIMITED CLAIMS COPYRIGHT TO THIS DRAWING WHICH MAY NOT BE USED FOR ANY PURPOSE OTHER THAN THAT PROVIDED IN THE CONTRACT BETWEEN THE OWNER/CLIENT AND THE ENGINEER WITHOUT THE EXPRESS CONSENT OF TATHAM ENGINEERING LIMITED.

**ACCEPTED FOR CONSTRUCTION EPCOR**

per .....  
Date: .....

**EPCOR**  
43 Stewart Road,  
Collingwood, Ontario  
L9Y 3Z5


No.	REVISION DESCRIPTION	DATE	ENGINEER STAMP
1.	1ST SUBMISSION	DEC 2022	
2.	ISSUED TO EPCOR FOR REVIEW	MAR 2023	
3.	2ND SUBMISSION	JULY 2023	
4.	3RD SUBMISSION	DEC 2023	




**CRANBERRY MARSH ESTATES**  
TOWN OF COLLINGWOOD

SITE PLAN - POWER LAYOUT

TATHAM ENGINEERING		
DESIGN: RJW	FILE: 120181	DWG: E2.1
DRAWN: RJW	DATE: OCT 2021	
CHECK: SRT	SCALE: AS SHOWN	




KEY PLAN



ELECTRICAL LEGEND	
	PROPOSED LUMINAIRE. REFER TO SPECIFICATIONS ON E3.3
	INDICATES GROUND ROD TO BE INSTALLED AT EACH END OF CIRCUIT LIGHT POLE LOCATION
	PROPOSED STREET LIGHT PEDESTAL WITH TAG
	PROPOSED STREET LIGHT CABLE(S) AND 53mmØ CONDUIT (PVC TYPE DB2). STREET LIGHT ONLY DUCTBANK.
	PROPOSED STREET LIGHT CABLE(S) AND 53mmØ CONDUIT (PVC TYPE DB2), IN JOINT TRENCH WITH HYDRO, GAS AND COMMUNICATIONS.

**2 STREETLIGHT ONLY DUCTBANK – NON-JOINT TRENCH**

- E3.1 - NTS, DIMENSIONS SHOWN IN MILLIMETRES (mm). DUCTBANK NOTES:
- PROVIDE FISH ROPE IN EACH SPARE (S) DUCT
  - GLUE ALL PVC JOINTS



**1 ELECTRICAL SITE PLAN – LIGHTING LAYOUT**


E3.1 - SCALE 1:500

**DISCLAIMER AND COPYRIGHT**  
 CONTRACTOR MUST VERIFY ALL DIMENSIONS AND BE RESPONSIBLE FOR SAME. ANY DISCREPANCIES MUST BE REPORTED TO THE ENGINEER BEFORE COMMENCING WORK. DRAWINGS ARE NOT TO BE SCALED.  
 TATHAM ENGINEERING LIMITED CLAIMS COPYRIGHT TO THIS DRAWING WHICH MAY NOT BE USED FOR ANY PURPOSE OTHER THAN THAT PROVIDED IN THE CONTRACT BETWEEN THE OWNER/CLIENT AND THE ENGINEER WITHOUT THE EXPRESS CONSENT OF TATHAM ENGINEERING LIMITED.


**ACCEPTED FOR CONSTRUCTION EPCOR**

per .....

Date: .....




No.	REVISION DESCRIPTION	DATE
1.	1ST SUBMISSION	DEC 2022
2.	ISSUED TO EPCOR FOR REVIEW	MAR 2023
3.	2ND SUBMISSION	JULY 2023
4.	3RD SUBMISSION	DEC 2023




**CRANBERRY MARSH ESTATES**  
 TOWN OF COLLINGWOOD

SITE PLAN – LIGHTING LAYOUT


<b>TATHAM ENGINEERING</b>	
DESIGN: RJW	FILE: 120181
DRAWN: RJW	DATE: OCT 2021
CHECK: SRT	SCALE: AS SHOWN
<b>DWG: E3.1</b>	



3 TYPICAL WIRING DETAIL FOR STREET LIGHT  
- NTS



1 "LC-A" SERVICE ENTRANCE POWER PANEL PEDESTAL INSTALLATION DETAIL  
- NTS, DIMENSIONS SHOWN IN MILLIMETRES (mm)




2 "LC-A" METERED PEDESTAL WIRING DIAGRAM  
- NTS, DIMENSIONS SHOWN IN MILLIMETRES (mm)

DISCLAIMER AND COPYRIGHT  
CONTRACTOR MUST VERIFY ALL DIMENSIONS AND BE RESPONSIBLE FOR SAME. ANY DISCREPANCIES MUST BE REPORTED TO THE ENGINEER BEFORE COMMENCING WORK. DRAWINGS ARE NOT TO BE SCALED.  
TATHAM ENGINEERING LIMITED CLAIMS COPYRIGHT TO THIS DRAWING WHICH MAY NOT BE USED FOR ANY PURPOSE OTHER THAN THAT PROVIDED IN THE CONTRACT BETWEEN THE OWNER/CLIENT AND THE ENGINEER WITHOUT THE EXPRESS CONSENT OF TATHAM ENGINEERING LIMITED.

ACCEPTED FOR CONSTRUCTION  
EPCOR  
per .....  
Date: .....



No.	REVISION DESCRIPTION	DATE
1.	1ST SUBMISSION	DEC 2022
2.	ISSUED TO EPCOR FOR REVIEW	MAR 2023
3.	2ND SUBMISSION	JULY 2023
4.	3RD SUBMISSION	DEC 2023



CRANBERRY MARSH ESTATES  
TOWN OF COLLINGWOOD  
LIGHTING DETAILS - SHEET 1

TATHAM ENGINEERING	
DESIGN: RJW	FILE: 120181
DRAWN: RJW	DATE: OCT 2021
CHECK: SRT	SCALE: AS SHOWN

DWG: E3.2

**H1 Pole**

**Pole Material:** Ø5" O.D. x .226 wall extruded aluminum welded to aluminum base plate.

**Base Cover:** Two piece square cast aluminum base cover attached to pole with stainless steel screws.

**Anchor Bolts:** 4 galvanized 19mm (3/4") x 609 6mm (24") long. Anchorbolts and template are supplied by HCI. (B.C. 8.5")

**Finish:** Electrostatically applied, thermoset polyester powdercoat finish.

**Colour:** Black RAL9011.

Tenon Top  
Pole Cap  
Cross Section  
Handhole  
Round Base Cover

Sales: KIM Designer: HOWARD  
Date: NOV 2022 Drawing No: 13225-V1  
Model: P424-2-5PC-24-RAL9011  
Project: Hill Ridge Homes

Please Note: Fabrication will not begin until the drawings are approved, signed and sealed by the E.I.C.

**HCI**  
HERITAGE CASTING & IRONWORKS LTD.  
1280 Fewster Drive, Mississauga, Ontario, Canada L4W 1A4  
Tel: (905) 238-2646 Fax: (905) 238-9090  
Toll Free Canada & USA 1-800-267-3175  
E: sales@hclighting.com WEB: www.hclighting.com

**HCI LIGHTING**  
HERITAGE CASTING & IRONWORKS LTD.  
1280 Fewster Drive  
Mississauga, ON L4W 1A4 Canada

**LED**

3000K CCT with no side shield diffuser meets criteria for Dark Sky Compliance

**SL20-2500L-3000K-120V-IES III (3)-DIM-HSS-PEC-FI-FTG(TOP)-9011 BLACK**

PRODUCT	LUMENS	CCT	VOLTAGE	OPTICS	OPTIONS	FITTER	FINIALS
SL20	Max 23,000 LUMENS	3000K 4000K 5000K 6000K =10% Variance	120v-277v	IES TYPE II (2) III (3) IV (4) V (5)	DIM Dimming control HSS House side shield PEC Integrated locking photocell	N/A	FI FJ

**DIFFUSER TYPE**  
CAC Clear acrylic  
FAC Frosted acrylic  
WAC White acrylic  
CPC Clear polycarbonate  
WPC White polycarbonate  
CTG Clear tempered glass  
FTG Flat tempered glass

**Color**  
Standard RAL  
6005 Green  
7012 Grey  
8019 Bronze  
9011 Black/Txt  
9016 White  
Custom RAL

LED Light  
UL LISTED  
ETL LISTED  
7 YEAR WARRANTY  
MADE IN CANADA  
HERITAGE ALUMINUM

**HCI Lighting Heritage**  
www.hclighting.com | 1.905.238.2648

**CONTRACTOR TO USE 13" BASE ABOVE GRADE**

NOTE: 1. ALL DIMENSIONS ARE IN NOMINAL FEET OR INCHES.  
2. TOP OF FOUNDATION SHALL BE TROWELED SMOOTH & LEVEL.  
3. CLASS OF CONCRETE SHALL BE 3000 P.S.I. CONCRETE SHALL BE VIBRATED.  
4. MINIMUM OF TWO SLEEVES REQUIRED FOR EACH CONC. FOUNDATION UNLESS OTHERWISE SHOWN.  
5. PROVIDE A 3/8" DIA. 1/2" STEEL COPPER COATED GROUND ROD ADJACENT TO POLES AS SPECIFIED ON PLAN AND CONNECT TO METAL.  
6. CONTRACTOR TO VERIFY OPENING SIZE IN POLE BASE PLATE PRIOR TO SETTING CONDUIT SLEEVES.  
7. SUBJECT TO SOIL CONDITIONS, REFER TO SOIL REPORT.  
8. FORM RELEASE AGENT HAS BEEN FACTORY APPLIED TO INSIDE SURFACE OF "ARTFORM".

OPTIONAL ALUMINUM COLOR ACCENT BAND  
FIN. GRADE  
DIVERSED (TO METE.)  
FIBER FORM  
30"  
2" POLYETHYLENE PIPE (REFER TO ELECTRICAL)  
ADAPT RIGID PVC TO POLYETHYLENE PIPE WITH ADAPTER COUPLING (REFER TO ELECTRICAL)

CAST-IN-PLACE ARCHITECTURAL CONCRETE BASE BY MEANS OF NEWAVEA 510R-LOW STYLE SINGLE USE ARTFORM CONCRETE FORM SUPPLIED BY ARTFORM INTERNATIONAL INC. TEL: 905-442-3225 www.artformsconcretebases.com

GALVANIZED STEEL "F" BOLTS AS SUPPLIED BY MANUFACTURER  
TOP OF CONVENTIONAL FIBER FORM AT 2" BELOW FIN. GRADE  
2" RIGID PVC CONDUIT SLEEVE 30" RADII (REFER TO ELECTRICAL)  
0.75" RIGID CONDUIT SLEEVE FOR GROUND CONNECTION AS REQUIRED & SPECIFIED-SEE DWG. (REFER TO NOTE 5)  
#46 REIN. RODS & #4 TIES  
1" Dia.  
LIGHTING POLE  
POLE BASE COVER  
LOCK NUTS  
LEVELING NUTS  
NEWAVEA 510R-LOW STYLE SINGLE USE ARTFORM CONCRETE FORM  
LIGHTING POLE  
FIN. GRADE  
TOP OF CONVENTIONAL FIBER FORM AT FIN. GRADE  
1" Dia.

**HIGH BASE**

**LOW BASE**

NOTE: Where applicable, this detail drawing should be modified to meet local requirements.

**ARTFORMS**  
NEWAVEA 510R

DRAWING TITLE  
LIGHTING POLE, FLAGPOLE, FLOODLIGHT, SIGN AND COLUMN BASE  
DATE  
JOB NO.  
SCALE  
DWG. NO.

PLOT @ 3/32"=1"

**LUMINAIRE**

**POLE**

886

7315mm

REFER TO CATALOG SHEETS ON THIS DRAWING FOR POLE, LUMINAIRE AND CONCRETE BASE SPECIFICATIONS

**1**  
E3.3  
-NTS  
**H1 POLE, LUMINAIRE AND CONCRETE BASE CATALOG SPECIFICATION SHEETS**

**2**  
E3.3  
-NTS  
**LUMINAIRE TYPE H1 INSTALLATION DETAIL**

**DISCLAIMER AND COPYRIGHT**  
CONTRACTOR MUST VERIFY ALL DIMENSIONS AND BE RESPONSIBLE FOR SAME. ANY DISCREPANCIES MUST BE REPORTED TO THE ENGINEER BEFORE COMMENCING WORK. DRAWINGS ARE NOT TO BE SCALED.

TATHAM ENGINEERING LIMITED CLAIMS COPYRIGHT TO THIS DRAWING WHICH MAY NOT BE USED FOR ANY PURPOSE OTHER THAN THAT PROVIDED IN THE CONTRACT BETWEEN THE OWNER/CLIENT AND THE ENGINEER WITHOUT THE EXPRESS CONSENT OF TATHAM ENGINEERING LIMITED.

**ACCEPTED FOR CONSTRUCTION**  
**EPCOR**

per .....  
Date: .....

**EPCOR**  
43 Stewart Road,  
Collingwood, Ontario  
L9Y 3Z5

No.	REVISION DESCRIPTION	DATE	ENGINEER STAMP
1.	1ST SUBMISSION	DEC 2022	
2.	ISSUED TO EPCOR FOR REVIEW	MAR 2023	
3.	2ND SUBMISSION	JULY 2023	
4.	3RD SUBMISSION	DEC 2023	

**CRANBERRY MARSH ESTATES**  
**TOWN OF COLLINGWOOD**


**TATHAM ENGINEERING**

DESIGN: RJW FILE: 120181 DWG:  
DRAWN: RJW DATE: OCT 2021  
CHECK: SRT SCALE: AS SHOWN

**LIGHTING DETAILS - SHEET 2**

**E3.3**

**1**  
E3.3  
-NTS  
**LUMINAIRE TYPE H1 INSTALLATION DETAIL**



KEY PLAN

Luminaire Schedule							
Symbol	Qty	Label	Arrangement	Description	LLF	Luminaire Lumens	Luminaire Watts
	8	H1	Single	HCI-SL20 Series	0.950	2500	20

**1 PHOTOMETRIC LUMINAIRE SCHEDULE**

E4.1 -NTS  
REFER TO DRAWING E3.3 FOR DETAILED POLE AND LUMINAIRE SPECIFICATIONS

Table 11-1: Lighting Design Criteria for Streets

Road:	Local
Pedestrian Conflict Area:	Low
Pavement Classification:	R3
Average Luminance Values:	0.3 cd/sq. m
Average Illuminance Values:	4.5 Lux
Uniformity Ratio Max (Avg/Min):	6.0:1 (MAX.)

Table 11-2: Recommended Design Criteria for Walkways Within Road Right of Way

Condition:	Low Pedestrian Activity
Average Illuminance Values:	2.0 Lux
Uniformity Ratio Max (Avg/Min):	5.0:1


Table 17-2: Recommended Maintained Illuminance Values for Parking Lots (basic requirements; not for security lighting)

Minimum Illuminance Values:	2.0 Lux
Uniformity Ratio Max (Max/Min):	20.0:1

Calculation Summary						
Label	CalcType	Units	Avg	Max	Min	Avg/Min
01-RW- Roadway	Illuminance	Lux	5.06	15.2	0.8	6.33
07-PA-Pathway	Illuminance	Lux	2.01	9.1	1.0	2.01
08-CU-Culdesac	Illuminance	Lux	6.06	15.0	0.7	8.66
09-TP-Property Line	Illuminance	Lux	0.00	0.0	0.0	N.A.

**2 ILLUMINATION SUMMARY (LUX)**

E4.1 -NTS



**3 ELECTRICAL SITE PLAN – PHOTOMETRIC LAYOUT (UNITS SHOWN IN LUX)**

E4.1 – SCALE 1:500

DISCLAIMER AND COPYRIGHT  
CONTRACTOR MUST VERIFY ALL DIMENSIONS AND BE RESPONSIBLE FOR SAME. ANY DISCREPANCIES MUST BE REPORTED TO THE ENGINEER BEFORE COMMENCING WORK. DRAWINGS ARE NOT TO BE SCALED.  
TATHAM ENGINEERING LIMITED CLAIMS COPYRIGHT TO THIS DRAWING WHICH MAY NOT BE USED FOR ANY PURPOSE OTHER THAN THAT PROVIDED IN THE CONTRACT BETWEEN THE OWNER/CLIENT AND THE ENGINEER WITHOUT THE EXPRESS CONSENT OF TATHAM ENGINEERING LIMITED.

**ACCEPTED FOR CONSTRUCTION  
EPCOR**

per .....  
Date: .....



43 Stewart Road,  
Collingwood, Ontario  
L9Y 3Z5

No.	REVISION DESCRIPTION	DATE
1.	1ST SUBMISSION	DEC 2022
2.	ISSUED TO EPCOR FOR REVIEW	MAR 2023
3.	2ND SUBMISSION	JULY 2023
4.	3RD SUBMISSION	DEC 2023

ENGINEER STAMP



**CRANBERRY MARSH ESTATES  
TOWN OF COLLINGWOOD**

SITE PLAN – PHOTOMETRIC LAYOUT



DESIGN: RJW	FILE: 120181	DWG:
DRAWN: RJW	DATE: OCT 2021	<b>E4.1</b>
CHECK: SRT	SCALE: AS SHOWN	